

H	DISCONNECT AND REMOVE ALL EXISTING ELECTRICAL DEVICES IN EXISTING CEILINGS AND WALLS WHICH ARE REQUIRED TO BE DEMOLISHED, WHETHER SHOWN OR NOT MAINTAIN CIRCUITS TO ALL REMAINING DEVICES.
I	REMOVE ALL EQUIPMENT, DEVICES, WIRING AND EXPOSED CONDUIT NOT BEING USED
J	VERIFY ALL DEMOLITION WORK REQUIRED BY THE LANDLORD WITH LANDLORD'S REPRESENTATIVE PRIOR TO BID.

6. COORDINATE ALL MOTOR OVERCURRENT PROTECTORS FURNISHED BY THIS CONTRACT WITH THE MACHINE EQUIPMENT INSTALLED. SIZE OVERLOADS BASED ON MOTOR NAMEPLATE FULL LOAD CURRENT AND SERVICE FACTOR. FUSES FOR MOTOR AND TRANSFORMER CIRCUITS SHALL BE DUAL ELEMENT, FUSES FOR OTHER "NON-INRUSH" LOADS SHALL BE FAST ACTING. ALL FUSES SHALL BE CURRENT LIMITING CLASS RK5 OR CLASS L UNLESS OTHERWISE NOTED.
FUSES SHALL BE PROVIDED WITH REJECTION TYPE FUSE HOLDERS.

37. THE CONTRACTOR SHALL PROVIDE ALL EQUIPMENT, MATERIALS AND LABOR TO COMPLETE ALL ELECTRICAL WORK IN A NEAT AND WORKMANLIKE MANNER AND IN ACCORDANCE WITH GOOD COMMERCIAL PRACTICE INCLUDING THE INSTALLATION OF ALL THE EQUIPMENT MATERIALS AND SYSTEMS AND THE FINAL CONNECTIONS TO THE OWNER'S EQUIPMENT AND FIXTURES AS REQUIRED BY THE OWNER. THE CONTRACTOR SHALL ALSO FURNISH TEMPORARY WIRING AND LIGHTING TO PROVIDE A MINIMUM OF 25 FC IN WORK AREAS FOR USE OF ALL THE TRADES DURING CONSTRUCTION AND THE INSTALLATION OF THE OWNERS FIXTURES. THE CONTRACTOR IS RESPONSIBLE TO REMOVE ALL TEMPORARY WIRING UPON COMPLETION OF CONSTRUCTION OF ALL TRADES.

	DUPLEX RECEPTACLE TAMPER-RESISTANT ABOVE COUNTER, GFCI.
	FLOOR BOX WITH DUPLEX RECEPTACLE FLOOR BOX, 120V, 20A - SEE PLANS FOR DETAILS.
	FLOOR BOX WITH QUADPLEX RECEPTACLE FLOOR BOX, 120V, 20A - SEE PLANS FOR DETAILS.
	SINGLE RECEPTACLE.
	SEE EQUIPMENT SCHEDULE AND NOTES.
	CEILING MOUNTED RECEPTACLE 20A, 120V.
	SPLIT-WIRED DUPLEX RECEPTACLE OUTLET.
	FUSED DISCONNECT SWITCH WITH DUAL NAME PLATE RATING.
	FUSED DISCONNECT SWITCH WITH MOTOR FUSES PER EQUIPMENT NAME PLATE RATING.
	NON-FUSIBLE DISCONNECT SWITCH.
	MOTOR OUTLET AND FLEX CONNECTION.
	METER, METER SOCKET.
	CIRCUIT BREAKER.
	GROUNDING ELECTRODE SYSTEM.
	UPPER GROUND ROD, U.S. WATER PIPE.
	PANELBOARD.
	TELEPHONE / DATA / COMBINATION DATA.
	CEILING MOUNTED WIRELESS ACCESS POINT.
	SECURITY CAMERA.
	CARD READER.
	HVAC SMOKE DUCT DETECTOR, S.M.D.
	FIRE SMOKE DAMPER, SMD.

	A	AMPERE
	AIC	AMPERE INTERRUPTING CAPACITY
	AFF	ABOVE FINISHED FLOOR
	AHJ	AUTHORITY HAVING JURISDICTION
	AWG	AMERICAN WIRE GAUGE
	C	CONDUIT
	CU	COPPER
	D	ONE WAY DISTANCE OF FEEDER OR BRANCH
	(E) / (N) / (RL)	EXISTING / NEW / RELOCATED
	EF	EXHAUST FAN
	EM	EMERGENCY
	GC	GENERAL CONTRACTOR
	GFI	GROUND FAULT INTERRUPTER
	G, GND	GROUND
	HP	HORSEPOWER
	ISC	SHORT CIRCUIT CURRENT
	MCB	MAIN CIRCUIT BREAKER
	MLO	MAIN LUG ONLY
	NEC	NATIONAL ELECTRICAL CODE
	NL	NIGHT LIGHT
	P	POLE
	PH	PHASE
	PROVIDE	FURNISH, INSTALL, CONNECT
	(R) / (RR)	REMOVE / REMOVE AND RELOCATE
	RMC	RIGID METAL CONDUIT
	SAD	SEE ARCHITECTURAL DRAWING
	SMD	SEE MECHANICAL DRAWING
	SPD	SEE PLUMBING DRAWING
	UON	UNLESS OTHERWISE NOTED
	V	VOLT
	VA	VOLT AMPERE
	VD	VOLTAGE DROP
	VFD	VARIABLE FREQUENCY DRIVE
	WP	WEATHERPROOF
	+42	SUBSCRIPT LOCATED NEXT TO THE DEVICE

SHEET INDEX	
DWG NO.	DRAWING TITLE
E0.0	ELECTRICAL GENERAL INFORMATION
E0.1	ELECTRICAL SPECIFICATIONS
ES1.0	ELECTRICAL SITE PLAN
E1.0	ELECTRICAL LIGHTING PLAN - 1ST FLOOR
E1.1	ELECTRICAL LIGHTING PLAN - 2ND FLOOR
E2.0	ELECTRICAL POWER PLAN - 1ST FLOOR
E2.1	ELECTRICAL POWER PLAN - 2ND FLOOR
E3.0	ELECTRICAL POWER & LIGHTING PLAN - ADU
E4.0	ELECTRICAL SINGLE-LINE DIAGRAM AND PANEL SCHEDULES

MARK	SYMBOL	DESCRIPTION	MANUFACTURER	MODEL NUMBER	MOUNTING	VOLTS	WATTS	NOTES
L1		4-INCH RECESSED LED DOWNLIGHT, 3000 K, 90+ CRI	JUNO	KC1BPFF 07LM 30K 90CRI 120 FRPC WITH 4JBLDT TRIM	RECESSED	120	15 W	JAB: PHASE DIMMABLE
L2		OPAL-GLASS LED PENDANT, 800 LM, 3000 K	GENERATION LIGHTING	6020EN3-15	SUSPENDED	120	9 W	INCLUDED JAB LAMP: FINAL FINISH BY OWNER/ARCHITECT
L3		LED WALL/BATH SCONCE, 800 LM, 5000 K	GENERATION LIGHTING	4919EN3-962	WALL	120	9 W	DAMP-LOCATION: INCLUDED JAB LAMP
L4		4-INCH ADJUSTABLE LED SPOTLIGHT, 3000 K, 90+ CRI	JUNO	WF4 4DJ 5SWWS 90CRI MW M16	RECESSED	120	8.99 W	JAB: WET-LOCATION; PHASE DIMMABLE
L5		EXTERIOR LED WALL LANTERN, PHOTOCELL, 800 LM, 3000 K	GENERATION LIGHTING	8909PN3-12	WALL	120	9 W	WET-LOCATION; COORDINATE REQUIRED MOTION/TIME CONTROL
L6		4-INCH WATERPROOF REGRESSED LED DOWNLIGHT, 3000 K	JUNO	WF4 REG 5SWWS 90CRI MW M16	RECESSED	120	8.99 W	WET-LOCATION; JAB: GFCI WHERE REQUIRED
L7		MAGNETIC ADJUSTABLE TRACK SPOTLIGHT, 25-DEGREE BEAM, 3000 K	PUREEDGE	T24M-2C-TUBS-SP-30K-WH	TRACK	120 INPUT / 24 VDC	9 W	JAB ONLY WITH LISTED UNIVERSAL POWER SUPPLY
L8		6-INCH LOW-PROFILE SURFACE LED CEILING LIGHT, 3000 K, 90+ CRI	JUNO	J5BC 6IN 30K 90CRI WH	SURFACE	120	12.6 W	JAB: WET-LOCATION; PHASE DIMMABLE
L9		TWO-CIRCUIT RECESSED MAGNETIC TRACK AND POWER SUPPLY	PUREEDGE	TR24M-2C-WH WITH PSB-96W-UNI-24VDC-T	RECESSED	120 INPUT / 24 VDC	96 W MAX	CONNECTED LOAD MUST REMAIN WITHIN POWER-SUPPLY RATING
L10		RECESSED MAGNETIC LINEAR PANEL/MODULE, 3000 K	PUREEDGE	T24M LINEA, 5 W/FT CONFIGURATION	RECESSED	120 INPUT / 24 VDC	5 W/FT	COORDINATE FINAL LENGTH AND POWER-SUPPLY CAPACITY
L11		CONCEALED LED STRIP, 3000 K, 90+ CRI	AMERICAN LIGHTING	HTLHD-WW-15 WITH COMPATIBLE LISTED DRIVER	SURFACE	120 INPUT / 24 VDC	3.65 W/FT	JAB: DAMP-LOCATION; SIZE DRIVER FOR INSTALLED LENGTH

GENERAL NOTES:

- A. BASIS OF DESIGN: 2023 CALIFORNIA ENERGY CODE FOR SINGLE-FAMILY RESIDENTIAL PERMITS FILED ON OR AFTER JANUARY 1, 2028.
- B. PERMANENTLY INSTALLED LIGHTING LUMINAIRES AND LIGHT SOURCES SHALL BE HIGH EFFICIENCY AND BEAR THE APPLICABLE JAS-2025 OR JAS-2025-2 MARKING. VERIFY THE EXACT ORDERING CODE IN THE CURRENT CEC COMPLIANCE DATABASE BEFORE PURCHASE.
- C. PROVIDE 300 x 90 x 90 MINIMUM LIGHT SOURCES UNLESS SPECIFICALLY NOTED OTHERWISE.
- D. RECESSED DIMMERS IN INSULATED CEILINGS SHALL BE 0 VOLTED, ARTIGHT, AND SEaled AT THE CEILING. PROVIDE DAMP OR WEt-LOCATOR LISTING AS REQUIRED BY THE INSTALLATION.
- E. PROVIDE TESTED DIMMERS AND DRIVERS COMPATIBLE WITH THE LIGHT LUMINAIRE, COORDINATE REQUIRED DIMMERS, VACUUMY SENSORS, AND OTHER RESIDENTIAL LIGHTING CONTROLS WITH THE LIGHTING PLAN.
- F. OUTDOOR BUILDING-MOUNTED LIGHTING SHALL HAVE MANUAL ON/OFF CONTROL AND THE REQUIRED PHOTOCONTROL WITH MOTION SENSOR, AUTOMATIC TIME SWITCH, OR ASTRONOMICAL TIME CLOCK. OVERRIDES SHALL RETURN TO AUTOMATIC OPERATION WITHIN SIX HOURS.

NOTES:

1. BASIS-OF-DESIGN PRODUCTS AND FINISHES SHALL BE CONFORMED WITH THE OWNER AND ARCHITECT BEFORE ORDERING.
2. SUBMIT THE COMPLETE MODEL NUMBER, CEC LISTING, DIMMER COMPATIBILITY, AND DAMP/WET LOCATION LISTING FOR REVIEW.
3. LOAD AND VOLTAGE TRACKING AND TIGHTNESS SHALL BE AS REQUIRED BY THE LIGHTING PLAN. PROVIDE LISTED 120V INPUT POWER-SUPPLYING LUMINAIRES COMPATIBLE WITH THE CONNECTED LIGHTINGS AND SIZES FOR THE CONNECTED LOAD. CONNECTED LOAD SHALL NOT EXCEED THE POWER-SUPPLY RATING. LIGHTING SUPPLIES AND DRIVERS IN ACCESSIBLE INSTALLATIONS, PROVIDE RELEVANT LISTING, MODEL NUMBER, ACCESSORIES FOR A COMPLETE AND OPERABLE SYSTEM.