

- I

DISCONNECT AND REMOVE ALL EXISTING ELECTRICAL DEVICES IN EXISTING CEILINGS AND WALLS WHICH ARE REQUIRED TO BE DEMOLISHED, WHETHER SHOWN OR NOT MAINTAIN CIRCUITS TO ALL REMAINING DEVICES.
- J

REMOVE ALL EQUIPMENT, DEVICES, WIRING AND EXPOSED CONDUIT NOT BEING USED
- J

VERIFY ALL DEMOLITION WORK REQUIRED BY THE LANDLORD WITH LANDLORD'S REPRESENTATIVE PRIOR TO BID.

- 6

GROUNDING CONDUCTORS ARE GENERALLY NOT SHOWN. GROUND AND BOND TOGETHER ALL EQUIPMENT, RACEWAYS, MOTORS, PANELBOARDS AND SWITCHBOARDS, ETC. IN ACCORDANCE WITH CEC ARTICLE 250. BONDING OF ALL INTERIOR METAL PIPING SHALL BE IN ACCORDANCE WITH CEC ARTICLE 250 AS FOLLOWS:
A. ALL INTERIOR METAL WATER PIPING SHALL BE BONDED TO ONE OR MORE GROUNDING ELECTRODES USED. THE BONDING JUMPER SHALL BE SIZED IN ACCORDANCE WITH CEC ARTICLE 250.
B. INTERIOR METAL PIPING THAT MAY BECOME ENERGIZED (i.e. GAS PIPING, ETC.), SHALL BE BONDED TO ONE OR MORE GROUNDING ELECTRODES USED. THE BONDING JUMPER SHALL BE SIZED IN ACCORDANCE WITH CEC ARTICLE 250, USING THE RATING OF THE CIRCUIT THAT MAY ENERGIZE THE PIPING SYSTEM.
C. INTERIOR METAL PIPING SYSTEM SEPARATED BY A PLUMBING EQUIPMENT (I.E. METER, WATER HEATER) SHALL BE PROVIDED WITH A BONDING JUMPER SIZED PER CEC ARTICLE 250. ALL GROUNDING ELECTRODE INSTALLED IN THE BUILDING (SINGLE OR MULTIPLE SERVICES) SHALL BE BONDED TOGETHER TO FORM A SINGLE GROUNDING ELECTRODE SYSTEM
- 8

INSTALL ALL WALL MOUNTED POWER, TELEPHONE AND DATA OUTLETS AT +15" A.F.F. TO BOTTOM OF THE BOX, UNLESS OTHERWISE NOTED. INSTALL ALL LIGHTING CONTROL SWITCHES, FIRE ALARM PULL STATIONS, AND WALL TELEPHONE JACKS AT +48" A.F.F. TO TOP OF THE BOX, UNLESS OTHERWISE NOTED.
- 9

CONDUCTOR PENETRATION OF FIRE RATED PORTIONS OF A STRUCTURE SHALL BE EFFECTIVELY SEALED AND SLEEVED WITH STEEL FLEX 3 FEET EACH SIDE OF THE PENETRATION, OR OTHER APPLIED METHODS.
- 10

FIRE ALARM CABLE SHALL BE INSTALLED IN CONDUIT WHERE REQUIRED BY CODE.
- 11

RECESSED LIGHT FIXTURES, INSTALLED WHERE THERE ARE INSULATION ARE REQUIRED TO BE I.C. RATED
- 12

ALL LIGHT SWITCHES NOT WITHIN SIGHT OF THE LUMINAIRES SHALL BE EQUIPPED WITH A PILOT LIGHT, EVEN IF NOT SHOWN IN THE DRAWINGS.
- 13

CONTRACTOR TO PROVIDE ALL REQUIRED SEISMIC SUPPORT WIRES FOR THE LIGHTING FIXTURES. PENDANT FIXTURES SHALL BE PROVIDED WITH SEISMIC SUPPORT WIRES SO AS NOT TO HIT ANYTHING ON A 45 DEGREE SWING AND AS REQUIRED BY THE AHJ.
- 14

ALL EQUIPMENT SHALL BE UL LISTED AND SHALL BE INSTALLED AS PER THEIR LISTINGS. INSTALLATION INSTRUCTION FOR ALL UL LISTED EQUIPMENT SHALL BE MADE AVAILABLE TO THE BUILDING INSPECTOR AT THE TIME OF INSPECTION. ALL DEVICES AND EQUIPMENT INSTALLED OUTDOORS OR EXPOSED TO THE WEATHER SHALL BE OF WEATHERPROOF CONSTRUCTION. ALL RECEPTACLES SHALL COMPLY WITH THE LATEST EDITION OF THE CEC, EVEN IF NOT SPECIFICALLY IDENTIFIED IN THE DRAWINGS (GFCI, AFCI, TAMPER RESISTANT, HOSPITAL GRADE, ETC.)
- 15

CONTRACTOR TO SUBMIT LOAD SUMMARY (SERVICE CARE SHEET) TO THE ELECTRIC UTILITY COMPANY FOR COORDINATION TO THE EXISTING SERVICE LATERAL/ENTRANCE CONDUCTOR AND ASSOCIATED UTILITY TRANSFORMER.
- 16

STRUCTURAL STEEL FIREPROOFING THAT WERE DAMAGED DURING CONSTRUCTION SHALL BE PATCHED AND REPAIRED BY THIS CONTRACTOR.
- 17

CONTRACTOR SHALL VERIFY FIELD CONDITIONS BEFORE SUBMITTING BID.
- 18

CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMITS, CERTIFICATES, ETC. REQUIRED.
- 19

WHERE REQUIRED, CONTRACTOR SHALL OBTAIN AND PAY FOR BOTH ROUGH AND FINAL UNDERWRITERS OR OTHER APPROVED INSPECTION AGENCY CERTIFICATES "ELECTRICAL INSPECTION". THESE CERTIFICATES SHALL BE PRESENTED WITH REQUEST FOR FINAL PAYMENT.
- 20

IT IS THE INTENT OF THESE PLANS TO PROVIDE A COMPLETE OPERATING ELECTRICAL SYSTEM. THIS CONTRACTOR SHALL FURNISH AND INSTALL ALL WIRING, EQUIPMENT, MATERIAL, ETC. REQUIRED, EXCEPT WHERE SPECIFICALLY NOTED AS BEING FURNISHED BY OTHERS. SHOULD THERE BE ANY QUESTIONS CONCERNING RESPONSIBILITY, THEY SHALL BE ADDRESSED TO ARCHITECT PRIOR TO BID. NO EXTRA CHARGES WILL BE ALLOWED.
- 21

ELECTRICAL SERVICE SHALL BE COORDINATED WITH THE EXISTING FIELD CONDITIONS.
- 22

CONSULT WITH CONTRACTORS FURNISHING HVAC EQUIPMENT TO VERIFY LOADS AND SECURE EXACT LOCATIONS (REFER TO HVAC DRAWINGS), WIRE AND CONECT TO ALL HVAC EQUIPMENT, INCLUDING CONTROLS AND THERMOSTATS.
- 23

CONTRACTOR SHALL MAKE ALL FINAL CONNECTIONS TO ALL CONTROLS, OWNER-SUPPLIED EQUIPMENT, MECHANICAL AND PLUMBING EQUIPMENT AS REQUIRED.
- 24

CIRCUIT NUMBER ON THE DRAWINGS ARE FOR IDENTIFICATION ONLY AND DO NOT INDICATE THE POSITION ON THE PANEL BOARD. CONNECT THE CIRCUITS WITH THE LIGHTEST LOADS AND THE RECEPTACLE CIRCUITS NEAR THE TOP OF THE PANEL, AND THE MORE HEAVILY LOADED CIRCUITS NEAR THE BOTTOM. BALANCE ALL CIRCUITS EVENLY BETWEEN PHASE SO THAT FEEDER WIRES CARRY APPROXIMATELY EQUAL CURRENT. ALL PHASES MUST BE BALANCED WITHIN 10% OR LESS. CONTRACTOR SHALL REBALANCE IF NECESSARY.
- 25

BRANCH CIRCUIT CONDUCTORS SHALL NOT BE LESS THAN NO. 12 AWG. THE INSULATION SHALL BE COLOR CODED, AND SHALL BE 600 VOLT, TYPE THHN/THWN COPPER.
- 26

CABLES IN HIGH TEMPERATURE AREAS SHALL HAVE INSULATION TYPE SUITABLE FOR THE TEMPERATURE. CABLES USED IN SPACES FOR ENVIRONMENTAL AIR SHALL CONFORM WITH APPLICABLE CEC REQUIREMENTS.

- 37

CONTRACTOR SHALL PROVIDE ALL EQUIPMENT, MATERIALS AND LABOR TO COMPLETE ALL ELECTRICAL WORK IN A NEAT AND WORKMANLIKE MANNER AND IN ACCORDANCE WITH GOOD COMMERCIAL PRACTICE INCLUDING THE INSTALLATION OF ALL THE EQUIPMENT MATERIALS AND SYSTEMS AND THE FINAL CONNECTIONS TO THE OWNER'S EQUIPMENT AND FIXTURES AS REQUIRED BY THE OWNER. THE CONTRACTOR SHALL ALSO FURNISH TEMPORARY WIRING AND LIGHTING TO PROVIDE A MINIMUM OF 25 FC IN WORK AREAS FOR USE OF ALL THE TRADES DURING CONSTRUCTION AND THE INSTALLATION OF THE OWNERS FIXTURES. THE CONTRACTOR IS RESPONSIBLE TO REMOVE ALL TEMPORARY WIRING UPON COMPLETION OF CONSTRUCTION OF ALL TRADES.
- 38

CONTRACTOR SHALL LABEL ALL JUNCTION BOX, OUTLETS, LIGHT SWITCH, ETC. WITH CIRCUIT NUMBER ON INTERIOR OF COVER PLATE.
- 39

CONTRACTOR SHALL PROVIDE SEISMIC RESTRAINTS AND SUPPORTS FOR ALL FLOOR AND CEILING MOUNTED ELECTRICAL EQUIPMENT TO RESIST EARTHQUAKE EFFECTS DETERMINED IN ACCORDANCE WITH THE BUILDING CODE.
- 40

THE CONTRACTOR SHALL BE RESPONSIBLE TO PROVIDE AND INSTALL ALL SUPPLEMENTARY SUPPORT, INCLUDING SUPPORT STEEL AS REQUIRED TO HANG ALL EQUIPMENT AND LIGHTING FROM THE EXISTING STRUCTURE IN ACCORDANCE WITH THE ARCHITECTURAL/STRUCTURAL SUPPORT AND LOADING CRITERIA.
- 41

IT IS THE RESPONSIBILITY OF THIS CONTRACTOR TO PROVIDE FULLY DIMENSIONED COORDINATION DRAWINGS FOR ALL OF HIS RESPECTIVE WORK. THESE DRAWINGS MUST BE FULLY COORDINATED WITH ALL EXISTING CONDITIONS. ALL HVAC, PLUMBING, FIRE PROTECTION, ELECTRICAL, LIGHTING, STRUCTURAL AND ARCHITECTURAL SYSTEMS PRIOR TO PREPARING COMPOSITE MULTI DISCIPLINE COORDINATION DRAWINGS.
- 42

ALL DISCONNECTING MEANS AND EQUIPMENT INDICATED ON THE DRAWING SHALL BE IDENTIFIED BY NAMEPLATE IN COMPLIANCE WITH THE CEC 110-22.
- 43

ALL WIRING FOR THE EMERGENCY LIGHTING AND EMERGENCY SYSTEMS SHALL BE INSTALLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE CEC ARTICLE 700.
- 44

THE WIRING METHODS AND MATERIALS INDICATED IN THE SPECIFICATIONS AND ON THE DRAWINGS SHALL BE INSTALLED AND CONNECTED IN ACCORDANCE WITH THE REQUIREMENTS OF THE CEC ARTICLE 300.
- 45

THE ELECTRICAL SERVICE AND DISTRIBUTION SYSTEM AS INDICATED ON THE RISER DIAGRAM AND MATERIALS INDICATED IN THE SPECIFICATIONS SHALL BE IN COMPLIANCE WITH THE REQUIREMENTS OF THE CEC ARTICLE 230.
- 46

ALL OVER CURRENT PROTECTION SHALL BE IN COMPLIANCE WITH THE CEC SECTION 240.
- 47

ALL GROUNDING REQUIREMENT S OF THE COMPLETE ELECTRICAL DISTRIBUTION SYSTEM AND AS INDICATED IN THE SPECIFICATIONS SHALL BE IN ACCORDANCE WITH CEC ARTICLE 250.
- 48

PRIOR TO ANY REQUIRED CUTTING AND PATCHING OF CONCRETE FLOOR AND/OR CUTTING OF ROOF CONTRACTOR SHALL COORDINATE WITH BUILDING ENGINEER, SEAL, ALL EXTERIOR AND FIREWALL PENETRATIONS.
- 49

FOR ALL LIGHTING FIXTURES MOUNTED IN HUNG CEILING THE GENERAL CONTRACTOR SHALL PROVIDE AND INSTALL INDIVIDUAL SUPPORT AT EACH CORNER OF RECESSED LIGHTING TRIFTER CONNECTED TO BUILDING STEEL ABOVE ALL CONDUIT AND MC CABLE MOUNTED ABOVE HUNG CEILING SHALL BE INDIVIDUALLY SUPPORTED IN THE SAME FASHION AS PER CEC REQUIREMENTS.
- 50

NO "DOUBLING UP" ON CIRCUIT BREAKERS OR CONDUCTOR SPLICES WITH IN PANEL BOARDS SHALL BE PERMITTED. THE CONTRACTOR SHALL PROVIDE JUNCTION BOXES ADJACENT TO PANELBOARDS AS REQUIRED TO SPLICE COMMON CIRCUITS CONNECTORS.
- 51

DO NOT SCALE FROM THESE DRAWINGS.
- 52

PLANS ARE PREPARED WITH REQUIRED BRANCH CIRCUITS INDICATED BY CIRCUITS NUMBERS, PROVIDE AND INSTALL ALL CONDUITS, CONDUCTORS, BOXES, MISCELLANEOUS FITTINGS, ETC. FOR A COMPLETE AND OPERABLE SYSTEM (HOME RUN SHOWN). BRANCH CIRCUIT INSTALLATION SHALL COMPLY WITH SPECIFICATIONS AND CEC.
- 53

NATIONALLY RECOGNIZED TESTING LABORATORY SHALL LIST ALL EQUIPMENT IN COMPLIANCE WITH 02 CEC ART. 110.3.
- 54

ALL CONDUITS SHALL MAINTAIN FIVE (5) FEET CLEARANCE IN FRONT OF HVAC SUPPLY AND RETURN.
- 55



CONTRACTOR TO PROVIDE CONDUIT EXPANSION COUPLINGS AND BONDING JUMPERS WHERE REQUIRED. REFER TO STRUCTURAL DRAWINGS FOR EXPANSION JOINT LOCATION.
- 56















PROVIDE IDENTIFIED HANDLE TIES FOR ALL MULT-WIRE BRANCH CIRCUITS PER CEC 210.4(B).
- 57

THE WORKING SPACES ABOUT THE ELECTRICAL EQUIPMENT SHALL BE MAINTAINED PER CEC 110.26(A) AND THE UTILITY COMPANY REQUIREMENTS. THE DEDICATED EQUIPMENT SPACE SHALL BE MAINTAINED PER CEC 110.26(E).
- 58

THE CONTRACTOR FOR THIS WORK IS REQUIRED TO READ THE SPECIFICATIONS AND REVIEW DRAWINGS OF ALL DIVISIONS OF WORK AND IS RESPONSIBLE FOR THE COORDINATION OF THIS WORK AND THE WORK OF ALL SUBCONTRACTORS WITH ALL DIVISIONS OF WORK. IT IS THIS CONTRACTOR'S RESPONSIBILITY TO PROVIDE ALL SUBCONTRACTORS WITH A COMPLETE SET OF BID DOCUMENTS.

CONTROL SCHEDULE					
MARK	DESCRIPTION	MANUFACTURER	MODEL NUMBER	MOUNTING	NOTES
D	PHASE-SELECTABLE LED DIMMER	LUTRON	MA-PRO	WALL	FORWARD-PHASE NEMA SSL 7A; MULTI-LOCATION WITH MA-R
VS	VACANCY SENSOR SWITCH - MANUAL-ON/AUTO-OFF	LUTRON	MS-VP55M	WALL	180 DEG PIR; TITLE 24; MULTI-LOCATION CAPABLE
S	DIGITAL ON/OFF SWITCH	LUTRON	MA-S8AM	WALL	SEPARATE CONTROL FOR NONDIMMED, CABINET, FAN, OR EXTERIOR LOADS
CDS	CABINET DOOR/DRAWER AUTOMATIC-OFF SWITCH	CABINET LIGHTING MFR	LISTED ASSEMBLY	CABINET	TURN LIGHT OFF WHEN OPAQUE DOOR OR DRAWER IS CLOSED
ATC	4-CIRCUIT ASTRONOMICAL TIME SWITCH	INTERMATIC	ET8415CR	INDOOR/OUTDOOR	EXTERIOR LIGHTING; 120-277 V; SEE NOTE 4
HS	BATHROOM EXHAUST-FAN HUMIDITY SENSOR	LUTRON	MS-HS3	WALL	ADJUSTABLE 50-80% RH; CALGREEN 4.506.1
GENERAL NOTES: A. ALL CONTROLS SHALL BE LISTED, COMPATIBLE WITH CONNECTED LED SOURCES/DRIVERS, AND INSTALLED PER 2025 CEC 150.0(K), SECTION 110.9, AND MANUFACTURER INSTRUCTIONS. B. FINAL DEVICE FINISH, COLOR, GANGING, MULTI-LOCATION ACCESSORIES, AND SMART-HOME/CENTRALIZED SYSTEM INTEGRATION SHALL BE COORDINATED WITH OWNER AND ARCHITECT. C. BASIS-OF-DESIGN MODELS MAY BE REPLACED WITH APPROVED EQUAL DEVICES PROVIDING IDENTICAL CODE-REQUIRED FUNCTIONALITY.					
NOTES: 1. PROVIDE D AT LIGHTING IN HABITABLE SPACES INCLUDING LIVING, DINING, KITCHEN, OFFICE, AND BEDROOM AREAS, EXCEPT WHERE SPECIFICALLY EXEMPTED BY 2025 CEC 150.0(K)(2F). 2. PROVIDE VS CONTROLLING AT LEAST ONE LUMINAIRE IN EACH BATHROOM, GARAGE, LAUNDRY ROOM, UTILITY ROOM, AND WALK-IN CLOSET. SENSOR SHALL PROVIDE AUTOMATIC-OFF AND MANUAL-OFF OPERATION. 3. CONTROL UNDERCABINET, UNDERSELF, DISPLAY-CABINET, AND SIMILAR ACCENT LIGHTING SEPARATELY FROM CEILING LIGHTING. PROVIDE CDS FOR LIGHTING INSIDE DRAWERS OR CABINETS WITH OPAQUE FRONTS OR DOORS. 4. CONTROL PERMANENTLY MOUNTED EXTERIOR LIGHTING BY MANUAL ON/OFF CONTROL PLUS ATC. ANY OVERRIDE TO ON SHALL AUTOMATICALLY RETURN TO NORMAL OPERATION WITHIN 6 HOURS. FIELD VERIFY AND REUSE EXISTING EXTERIOR CONTROL INFRASTRUCTURE WHERE FEASIBLE. 5. CONTROL LIGHTING INTEGRAL TO EXHAUST FANS INDEPENDENTLY FROM THE FAN. PROVIDE HS FOR EACH BATHROOM EXHAUST FAN SERVING A ROOM WITH A TUB OR SHOWER, UNLESS THE FAN IS PART OF THE WHOLE-HOUSE VENTILATION SYSTEM. 6. NO SWITCH OR OTHER CONTROL SHALL BYPASS A CODE-REQUIRED DIMMER, OCCUPANCY SENSOR, OR VACANCY SENSOR. COORDINATE THREE-WAY AND MULTI-LOCATION CONTROLS ACCORDINGLY. 7. BLANK ELECTRICAL BOXES MORE THAN 5 FEET ABOVE FINISHED FLOOR SHALL BE SERVED BY A DIMMER, VACANCY SENSOR, LOW-VOLTAGE WIRING, OR FAN-SPEED CONTROL; TOTAL SHALL NOT EXCEED THE NUMBER OF BEDROOMS. 8. VERIFY CONNECTED LOAD TYPE, RATING, DIMMABILITY, NEUTRAL REQUIREMENTS, AND DEVICE COMPATIBILITY BEFORE ORDERING.					

LIGHTING FIXTURE SCHEDULE									
MARK	SYMBOL	DESCRIPTION	MANUFACTURER	MODEL NUMBER	MOUNTING	VOLTS	WATTS	NOTES	
L1		4-INCH RECESSED LED DOWNLIGHT, 3000 K, 90+ CRI	JUNO	IC1JBPF 07LM 30K 90CRI 120 FRPC WITH 4JBLDT TRIM	RECESSED	120	15 W	JAB; PHASE DIMMABLE	
L2		OPAL-GLASS LED PENDANT, 800 LM, 3000 K	GENERATION LIGHTING	6020EN3-15	SUSPENDED	120	9 W	INCLUDED JAB LAMP; FINAL FINISH BY OWNER/ARCHITECT	
L3		LED WALL/BATH SCONCE, 800 LM, 3000 K	GENERATION LIGHTING	49119EN3-962	WALL	120	9 W	DAMP-LOCATION; INCLUDED JAB LAMP	
L4		4-INCH ADJUSTABLE LED SPOTLIGHT, 3000 K, 90+ CRI	JUNO	WF4 ADJ 5WW5 90CRI MW M6	RECESSED	120	9.99 W	JAB; WET-LOCATION; PHASE DIMMABLE	
L5		EXTERIOR LED WALL LANTERN, PHOTOCELL, 800 LM, 3000 K	GENERATION LIGHTING	8909PEN3-12	WALL	120	9 W	WET-LOCATION; COORDINATE REQUIRED MOTION/TIME CONTROL	
L6		4-INCH WATERPROOF REGRESSED LED DOWNLIGHT, 3000 K	JUNO	WF4 REG 5WW5 90CRI MW M6	RECESSED	120	8.99 W	WET-LOCATION; JAB; GFCI WHERE REQUIRED	
L7		MAGNETIC ADJUSTABLE TRACK SPOTLIGHT, 25-DEGREE BEAM, 3000 K	PUREEDGE	T24M-2C-TUBS-SP-30K-WH	TRACK	120 INPUT / 24 VDC	9 W	JAB ONLY WITH LISTED UNIVERSAL POWER SUPPLY	
L8		6-INCH LOW-PROFILE SURFACE LED CEILING LIGHT, 3000 K, 90+ CRI	JUNO	JSBC BIN 30K 90CRI WH	SURFACE	120	12.6 W	JAB; WET-LOCATION; PHASE DIMMABLE	
L9		TWO-CIRCUIT RECESSED MAGNETIC TRACK AND POWER SUPPLY	PUREEDGE	TR24M-2C-WH WITH PSB-98W-4IN-24VDC-T	RECESSED	120 INPUT / 24 VDC	96 W MAX	CONNECTED LOAD MUST REMAIN WITHIN POWER-SUPPLY RATING	
L10		RECESSED MAGNETIC LINEAR PANEL/MODULE, 3000 K	PUREEDGE	T24M LINEA, 5 WIFT CONFIGURATION	RECESSED	120 INPUT / 24 VDC	5 WIFT	COORDINATE FINAL LENGTH AND POWER-SUPPLY CAPACITY	
L11		CONCEALED LED STRIP, 3000 K, 90+ CRI	AMERICAN LIGHTING	HTLHD-WW-16 WITH COMPATIBLE LISTED DRIVER	SURFACE	120 INPUT / 24 VDC	3.65 WFT	JAB; DAMP-LOCATION; SIZE DRIVER FOR INSTALLED LENGTH	
GENERAL NOTES: A. BASIS OF DESIGN: 2025 CALIFORNIA ENERGY CODE FOR SINGLE-FAMILY RESIDENTIAL PERMITS FILED ON OR AFTER JANUARY 1, 2026. B. PERMANENTLY INSTALLED INDOOR LUMINAIRES AND LIGHT SOURCES SHALL BE HIGH EFFICACY AND BEAR THE APPLICABLE JAB-2025 OR JAB-2025-E MARKING. VERIFY THE EXACT ORDERING CODE IN THE CURRENT CEC APPLIANCE DATABASE BEFORE PURCHASE. C. PROVIDE 3000 K, 90 CRI MINIMUM LIGHT SOURCES UNLESS SPECIFICALLY NOTED OTHERWISE. D. RECESSED LUMINAIRES IN INSULATED CEILINGS SHALL BE IC RATED, AIRTIGHT, AND SEALED AT THE CEILING. PROVIDE DAMP-OR WET-LOCATION LISTING AS REQUIRED BY THE INSTALLATION. E. PROVIDE LISTED DIMMERS AND DRIVERS COMPATIBLE WITH THE EXACT LUMINAIRE. COORDINATE REQUIRED DIMMERS, VACANCY SENSORS, AND OTHER RESIDENTIAL LIGHTING CONTROLS WITH THE LIGHTING PLAN. F. OUTDOOR BUILDING-MOUNTED LIGHTING SHALL HAVE MANUAL ON/OFF CONTROL AND THE REQUIRED PHOTOCONTROL WITH MOTION SENSOR, AUTOMATIC TIME SWITCH, OR ASTRONOMICAL TIME CLOCK. OVERRIDES SHALL RETURN TO AUTOMATIC OPERATION WITHIN SIX HOURS. NOTES: 1. BASIS-OF-DESIGN PRODUCTS AND FINISHES SHALL BE CONFIRMED WITH THE OWNER AND ARCHITECT BEFORE ORDERING. 2. SUBMIT THE COMPLETE MODEL NUMBER, CEC JAB LISTING, DIMMER COMPATIBILITY, AND DAMP/WET LOCATION LISTING FOR REVIEW. 3. LOW-VOLTAGE TRACK AND LED STRIP SYSTEM VOLTAGES SHOWN ARE SECONDARY VOLTAGES. PROVIDE LISTED 120V-INPUT POWER SUPPLY(S) COMPATIBLE WITH THE CONNECTED LIGHTING AND SIZED FOR THE CONNECTED LOAD. CONNECTED LOAD SHALL NOT EXCEED THE POWER-SUPPLY RATING. LOCATE POWER SUPPLIES AND DRIVERS IN ACCESSIBLE, VENTILATED LOCATIONS. PROVIDE ALL REQUIRED WIRING, CONNECTORS, AND ACCESSORIES FOR A COMPLETE AND OPERABLE SYSTEM.									

	DUPLEX RECEPTACLE (TAMPER-RESISTANT) ABOVE COUNTER, GFCI
	FLOOR BOX WITH DUPLEX RECEPTACLE, 120V, 20A - SEE PLANS FOR LOCATION
	FLOOR BOX WITH QUADPLEX RECEPTACLE, 120V, 20A - SEE PLANS FOR LOCATION
	SINGLE RECEPTACLE, SEE EQUIPMENT SCHEDULE AND NOTES
	CEILING MOUNTED RECEPTACLE, 20A, 125V
	SPLIT-WIRED DUPLEX RECEPTACLE OUTLET
	FUSED DISCONNECT SWITCH WITH DUAL NAME PLATE RATING
	FUSED DISCONNECT SWITCH WITH MOTOR FUSES PER EQUIPMENT NAME PLATE RATING
	NON-FUSIBLE DISCONNECT SWITCH
	MOTOR OUTLET AND FLEX CONNECTION
	METER, METER SOCKET
	CIRCUIT BREAKER
	GROUNDING ELECTRODE SYSTEM, UFER, GROUND ROD, U.G. WATER PIPE, ETC.
	PANELBOARD
	TELEPHONE / DATA / COMBINATION DATA
	CEILING MOUNTED WIRELESS ACCESS POINT
	SECURITY CAMERA
	CARD READER
	HVAC SMOKE DUCT DETECTOR, S.M.D.
	FIRE SMOKE DAMPER, SMD
	A AMPERE
	AIC AMPERE INTERRUPTING CAPACITY
	AFF ABOVE FINISHED FLOOR
	AHJ AUTHORITY HAVING JURISDICTION
	AWG AMERICAN WIRE GAUGE
	C CONDUIT
	CU COPPER
	D ONE WAY DISTANCE OF FEEDER OR BRANCH
	(E) / (N) / (RL) EXISTING / NEW / RELOCATED
	EF EXHAUST FAN
	EM EMERGENCY
	GC GENERAL CONTRACTOR
	GFI GROUND FAULT INTERRUPTER
	G, GND GROUND
	HP HORSEPOWER
	ISC SHORT CIRCUIT CURRENT
	MCB MAIN CIRCUIT BREAKER
	MLO MAIN LUG ONLY
	NEC NATIONAL ELECTRICAL CODE
	NL NIGHT LIGHT
	P POLE
	PH PHASE
	PROVIDE FURNISH, INSTALL, CONNECT
	(R) / (RR) REMOVE / REMOVE AND RELOCATE
	RMC RIGID METAL CONDUIT
	SAD SEE ARCHITECTURAL DRAWING
	SMD SEE MECHANICAL DRAWING
	SPD SEE PLUMBING DRAWING
	UON UNLESS OTHERWISE NOTED
	V VOLT
	VA VOLT AMPERE
	VD VOLTAGE DROP
	VFD VARIABLE FREQUENCY DRIVE
	WP WEATHERPROOF
	+42 SUBSCRIPT LOCATED NEXT TO THE DEVICE

SHEET INDEX	
DWG NO.	DRAWING TITLE
E0.0	ELECTRICAL GENERAL INFORMATION
E0.1	ELECTRICAL SPECIFICATIONS
ES1.0	ELECTRICAL SITE PLAN
E1.0	ELECTRICAL LIGHTING PLAN - 1ST FLOOR
E1.1	ELECTRICAL LIGHTING PLAN - 2ND FLOOR
E2.0	ELECTRICAL POWER PLAN - 1ST FLOOR
E2.1	ELECTRICAL POWER PLAN - 2ND FLOOR
E3.0	ELECTRICAL POWER & LIGHTING PLAN - ADU
E4.0	ELECTRICAL SINGLE-LINE DIAGRAM AND PANEL SCHEDULES